

Good Faith Deposit

- Since you are asking for different options , what price should we use for the bond ?

***You can use the lowest bid total for the good faith deposit**

AV Construction Administration Schedule:

A. Include (8) 30-min meetings to attend weekly construction meetings, which will be hosted by SitelogIQ. This assumes 2 weeks in July, 4 weeks in August 2026, 2 weeks in September.

- Can this be virtual ?

***Yes, these will be virtual**

A. Platform capabilities with common conferencing platforms such as Teams, Google Meets, Zoom, etc.

- Can you expand on the expected functionality ? (it does not seem like video conferencing is applicable to this system)

***The district uses Team primarily. The intent was in case there was a system proposed that had built in capabilities or a display that has built in compute that it would be capable with such platforms**

E. Integrate audio system with building PA system (FrontRow) or provide separate PA speakers.

- Is it possible to get an analog audio output of the paging system at the AV rack location ?

***A relay can be provided on the FrontRow system for AV integrators to tap into.**

O. Will be responsible for termination of Cat6 cables runs provided by electrical contractor.

- Please elaborate on what this scope entails

***The electrical contractor for the construction side of the project will be providing network cabling and pathways for low voltage devices such as Wi-Fi AP's, cameras, etc. If possible the A/V vendor will be responsible for terminating all of those cables in the new A/V rack to be installed in the A/V control room**

F. Mobile Lectern and supporting equipment.

- Do you have an example of what you are looking for ? What supporting equipment do you want provided ?

***A mobile podium capable of having a mic stand and display connections. We are looking for something a presenter could use to hold a laptop or other device and display on the screens. A wall plate would be required to connect the lectern when in use. Multiple perimeter wall connection points are provided throughout the Multi-Purpose room.**