

Aurora School Retaining Wall Scope of Work

- Preston County Schools is seeking bids on demolishing and building a retaining wall at Aurora Elementary School.
- The scope of work will include:
 - Demolishing and removing 66 feet of existing railing and a 6-foot-high retaining wall including disposing and hauling debris.
 - Demolishing and removing 37 feet by 6 feet concession deck, disposing and hauling.
 - Remove existing ball field rail tie steps, disposing and hauling.
 - Perform mass excavation 6 feet wide by approx. 7 feet deep by 103 feet long, including exposing the concession stand foundation. Tamp and prepare the sub-base footing for the installation of precast bin blocks. Backfill the retaining wall area using approximately 8 loads of 26T clean stone with permeable landscape fabric for silt protection.
 - Ensure proper framing adjustments and structural stabilization adjacent to the new retaining wall. Drainage -Install and adequate French drain system behind the new retaining wall along the exposed concession foundation.
 - Run standard 6-inch discharge pipe to daylight at the rear parking lot/lawn area for proper water management. Retaining wall; Install 22 precast bin blocks measuring 3 feet by 3 feet by 6 feet to construct wall. Install 12 smooth concrete cap stones on top of retaining wall. Install 42": high Pickett railing w/ 3.5" toe rail height in 8 ft section between posts.
- Sealed bid packets must be received no later than 12 PM on Oct 2, 2026.
- The Preston County Board of Education reserves the right to reject any or all bids.
- A pre-bid meeting for interested vendors is set for September 23, 2026 at Aurora School at 1 PM.
- General questions related to this post may be directed to Mr. Bill Larue at (304) 329-0580 ext. 3231 or William.larue@k12.wv.us.