NCA
ARCHITECTS · PLANNERS · AIA
Celebrating 32 Years of Quality Design & Excellent Client Service
1306 Rio Grande Blvd. NW, Albuquerque, NM 87104 • 505.255.6400 Voice • 505.268.6954 Fax
www.nca-architects.com info@nca-architects.com

ADDENDUM # 002

DATE: 10/21/2021

ARCHITECT
NCA Architects
Albuquerque, NM

PROJECT
A1912.1, A1912.2. A1912.3
BPS– ES and MS Systems and Security Improvements
PSFA Project Number: S19-004, T19-077, T19-078
Construction RFP Number: 2021-061-007

OWNER
Bernalillo Public Schools and the NM Public Schools Facility Authority (PSFA)

This addendum forms a part of the Contract Documents and modifies the original specifications and drawings dated 06.02.2021. Acknowledge receipt of this addendum in the space provided in the Bid Form. Failure to do so may subject the bidder to disqualification.

A. GENERAL INFORMATION RESPONSE THAT APPLY TO BASE BID, BID LOT 001, BID LOT 002, BID LOT 003, BID LOT 004 AND TO PERMIT 001 AND PERMIT 002.

B. QUESTIONS AND RESPONSES

Q1: Plan pages and the Spec book are calling for a 5' tall chain link fence. If adjacent existing fence is a different height, should I bid 5' tall or what is existing.
Response: At the areas where new chain link fence is specified, the new chain link fence should match the height of the existing adjacent fence. The 5'-0" dimension is an approximate height. As designated in the Drawing notes, the actual height of the existing fence will need to be field verified.

Q2: 32-3113, Part 2.2 Fence Framing is calling for 2 3/8" diameter line posts and 1 7/8" diameter terminal/end/corner posts. Should that be reversed?
Response: Yes. The Line posts should be 1-7/8" and the terminal/end/corner posts should be 2-3/8".

Q3: Does the fence have a bottom rail or bottom tension wire?
Response: Yes. The fence has a bottom rail per specification 32-3113-2.2-3 and tension wire per specification 32-3113-2.3.

END OF ADDENDUM #002