Fremont Community Schools
Fremont High School Tennis Addition

ADDENDUM #1
Date

NOTICE TO BIDDERS

YOU ARE HEREBY NOTIFIED TO INCORPORATE THE FOLLOWING CHANGES AND/OR ADDITIONS TO THE DRAWINGS AND SPECIFICATIONS FOR THE ABOVE **REFERENCED PROJECT. EACH BIDDER SHALL** SIGN ONE COPY OF THIS **ADDENDUM** AND **SUBMIT** ONLY **THE ACKNOWLEDGEMENT PAGE WITH THEIR** BID.

EACH CONTRACTOR RESPONSIBLE TO **INCLUDE ALL APPLICABLE** ITEMS **INTO** THEIR RESPECTIVE BID REGARDLESS OF HEADING **THEY** ARE LISTED UNDER THIS ADDENDUM.

Specification Items:

1. COMMENCEMENT OF WORK
   Work may begin in Fall of 2026 but is not required. Final Completion July 16th, 2027

2. PRESS BOX NOT PART OF BID
   No work for the press box will be required: some sidewalk work will be necessary to create access to new tennis courts. See plans for revised areas.

3. HOT-MIX ASPHALT PAVING
   1. Part 1 — General. 1.4 System Description, A. 1: Standard Specification shall current INDOT specifications.
   2. Part 2 — Products. B. Fine aggregate, 2: Only limestone aggregate 1s acceptable for surface mix to minimize impurities which could interact with the tennis surface coats.

Drawing Items:

1. Sheet Cl.0. Tennis Courts
   1. See revised demolition areas

2. Sheet C2.0. Tennis Courts
   1. See revised construction area

3. Sheet C2.1. Tennis Courts
   1. See revised construction area

4. Sheet C4.0. Tennis Courts and Details
    1. See revised Sidewalk Detail
    2. See revised Asphalt Detail
    3. See revised Pipe Detail

Fremont Community Schools
Fremont High School Tennis Court Addition

ADDENDUM #1

Date:

****
ACKNOWLEDGMENT OF RECEIPT
****

COMPANY	SIGNATURE & DATE