



ADDENDUM #1
BID #2027-02
STRATFORD ARBORETUM PROJECT
KETCHAM ROAD & PHILO STREET

6th August, 2026 – It is intended that this Addendum incorporating the following corrections, revisions, additions, deletions and clarifications become part of the Contract Documents.

Requests for Information (RFI):

1. Summary of work spec section 01 11 00 1.5A states “WORK BY OTHERS A. Work associated with installation of Bus Shelter. This is not NIC (not in contract) and is the responsibility of the Town of Stratford.”

There is a bid form item #38 asking for LS cost for installation of bus shelter.

Please clarify bus shelter.

Who is purchasing?

Who is installing?

Response: The bus shelter will be purchased by the Town of Stratford to be installed by the Contractor. Shelter will be prefabricated by Brasco International to meet GBT specifications. Details below.
Note there is 30-week lead-time from order approval.

Item #: SL-0512-F-C-RB-AC-TG-0-0-0

Description: 5' x 12' Slimline Series Aluminum Structure with Heavy Duty Anchor Boots Four-Sided; Full Rear and Side Walls; Front-Centered Windscreen with Two ADA Openings Clear Anodized Aluminum Finish Reverse Barrel Roof with White Acrylic Glazing and 2.5" Fascia with Integral Gutter 1/4" Clear Tempered Safety Glass Wall Panels.

2. Standard CB have 4' sump. Double CB have 2' sump.
Please verify sump depths.

Response: Please use 2' sumps for all catch basins.

Name and Title of Authorized Rep (Printed)

Signature

Date