ADDENDUM NO. 1

April 7, 2026

This Addendum No. 1 is hereby made a part of the specifications and drawings and shall become a part of the Contract Documents. Receipt of this Addendum shall be acknowledged on Page 1 of the Contractor's Bid Form.

GENERAL

No submitted substitutions have been approved.

Item #1: Specification Section Replacements

Replace the following Specification Sections with updated sections attached, dated February 27th, 2026:

274100 - COMMON WORK RESULTS FOR AUDIOVISUAL SYSTEMS
274120 - THEATER AUDIOVISUAL SYSTEMS
274125 - BACK OF HOUSE SPACES AUDIOVISUAL SYSTEMS

Item #2: Project Questions

1. Is the projector intended to be suspended from the ceiling or wall mounted to the front of the control booth as the equipment list suggests? Appendix A - 27 41 20 - AUDITORIUM Item #4
   - ABD RESPONSE: Refer to 1/AV0-1 for projector mounting configuration, with Unistrut support to be provided under JOC. Disregard reference to "wall" in Appendix 'A'.
2. QTY Discrepancy - Oneline diagram AV9-1 shows (8) WMR-01 (Shure ULXD4Q) wireless receivers, Appendix A - 27 41 20 - AUDITORIUM: AUDIOVISUAL SYSTEMS Item #46 shows a quantity of (6). Please advise.
   - ABD RESPONSE: Verify with SPS Purchasing that the correct version of 27 41 20 – Appendix 'A' has been issued. The "Issued for Bid" version should indicate a quantity of eight (8) for this item.
3. QTY Discrepancy - Appendix A - 27 41 20 - AUDITORIUM Item #49 Specs (3) Shure SBRC with (4) SBC-AX Charging modules each. 28 Transmitters are specified. Specified quantity of charging only supports charging (24) batteries simultaneously per 27 41 20 - 1.3, C., 6., g.
   - ABD RESPONSE: This is still the intended quantity. We anticipate that the rare need for multiple consecutive nights of 32 transmitters in-use, will require the owner to take pains to manage the charging cycle for these batteries to ensure availability.
4. Wireless handheld mics transmitters - Appendix A - 27 41 20 - AUDITORIUM Item #48 Specifies Shure UXLD2/SM87 Transmitter which is a supercardioid capsule. This contradicts 27 41 20 - 1.3, C., 6., d. where a cardioid capsule is mentioned. Note that SM87 capsule is still available but only in certain frequencies, but not the band that is likely for the physical location of the project. Please advise.

- ABD RESPONSE: The specification of the supercardioid capsule is the design intent for this item. This will provide best gain-before-feedback when used near onstage monitors and we generally specify condenser capsules for handheld units to be used by the general public, with increased sensitivity and reduced proximity effect for non-technical speakers.

5. Existing wireless equipment - 27 41 20 - 1.3, C., 6., b. & c. specify existing antenna distribution and log-periodic antennae that are to be reused. Items 445 & 45 on the Appendix equipment list appear to be redundant to the existing equipment. Which is intended? Please advise.

   - ABD RESPONSE: Verify with SPS Purchasing that the correct version of 27 41 20 – Appendix 'A' has been issued. The current version should indicate new antenna and distribution. These should also appear in the current version of Appendix 'A'.

6. QTY Discrepancy - Oneline diagram AV9-1 shows (2) SB-01 (Allen & Heath AH-DT168) stage boxes, Appendix A - 27 41 20 - AUDITORIUM Item #43 shows a quantity of (1). Please advise.

   - ABD RESPONSE: The specification quantity of one (1) is correct and should take precedence over the schematic diagram quantity noted.

7. PIC-01 - Custom Wall Plate for Production Intercom Connectivity - quantity of (5) shown on Appendix A - 27 41 20 - AUDITORIUM Item #59. PIC-01 is missing from custom plate details on AV8-1. AV9-1 shows (3): (2) on Stage Apron, (1) Tech Booth. Drawing AV1-B shows only (1) on the Stage Apron, and also shows a "PIC-01A" on the front wall of the Tech Booth. Please correct quantities and locations.

   - ABD RESPONSE: Correct quantity should be two (2) PIC-01 panels, which are not detailed on AV8-1, as they may be off-the-shelf XLR type panels and/or Decora style panels and inserts. We can revised 27 41 20 Appendix 'A' to match.

8. Ceiling speaker types S-03A & S-03B are specified in Appendix A 27 41 25 - BACK OF HOUSE SPACES items #7 & 8. Drawing Sheet AV2-B Shows Speaker Type S-03 in Corridor N101G, Rooms 14 & 16 and the south corridor. There is no indication in these areas which speaker type is needed or ceiling type. The quantity of S-03 speakers shown on AV2-B does not match what is specified in Appendix A BOH. Please advise.

   - ABD RESPONSE: Verify with SPS Purchasing that the correct version of 27 41 25 – Appendix 'A' has been issued. The "Issued for Bid" version should denote "QTY. PER PLANS" for these items.

9. Draper, Inc. 114614TH - Paragon V Projection Screen as shown on Appendix A - 27 41 20 - AUDITORIUM Item #20 does not specify low voltage control of the screen as it is an option to the specified model and not included. Diagram on AV9-0 shows an LVC-01 at the screen connected to the GPIO output of DSP-01. LVC-01 is not specified. Please advise.

   - ABD RESPONSE: The Electric Front Projection Screen Schedule on sheet AV6-0 denotes the LVC-IV controller for the screen specified. Provide accordingly.

10. QTY Discrepancy - VC-01, VC-02. Appendix A 27 41 25 - BACK OF HOUSE SPACES items #1 & 2. VC-01 is shown in (4) locations on AV1-B and AV9-1. Only (3) are specified in appendix. VC-02 is not shown on any drawings. Is VC-02 intended to be in the specification? Please advise.

- ABD RESPONSE: Verify with SPS Purchasing that the correct version of 27 41 25 – Appendix 'A' has been issued. The "Issued for Bid" version should denote the quantity shown on the drawings for these items.

11. QTY Discrepancy - FPD-01, FPD-02. Appendix A 27 41 25 - BACK OF HOUSE SPACES: AUDIOVISUAL SYSTEMS items #2 (QTY 4) & 4 (QTY 1). FPD-1 is shown in (3) locations, FPD-02 in (1) location on AV1-B and AV9-1. Quantities shown on the floorplan don't match spec'd quantities in Appendix A BOH. This also affects the number of spec'd decoders listed in Item #6. Please advise.

    - ABD RESPONSE: Verify with SPS Purchasing that the correct version of 27 41 25 – Appendix 'A' has been issued. The "Issued for Bid" version should denote the quantity shown on the drawings for these items.

12. Equipment Rack Specs: 27 41 20 - 1.3, I., 2. specifies storage drawers with foam inserts and rear rack rail. Foam inserts and rear rack rail are not spec'd in Appendix A - 27 41 20 - AUDITORIUM: AUDIOVISUAL SYSTEMS Item #58. Please advise.

    - ABD RESPONSE: Verify with SPS Purchasing that the correct version of 27 41 20 – Appendix 'A' has been issued. The "Issued for Bid" version should denote the drawers and accessory items shown and called out in the narrative. Other items should be provided under item 66 as miscellaneous.

13. Studio Monitor Specs: 27 41 20 - 1.3.C.9 says "Provide and integrate a pair of desktop powered studio monitors to allow for monitoring of FoH audio within the Control Room, for use by crew in that position." No equipment is specified for this paragraph. Please advise.

    - ABD RESPONSE: Strikethrough this line in the specification. The windows of this space are intended to be removed under a separate JOC contract, which will allow direct monitoring of audio from the House. There are existing self-powered monitors (ETR/OFE) that may be reused by the owner as production equipment, when and if needed.

14. A quantity of XLR Microphone cables for mics and stage monitors are not specified. Ethercon Data patch cables are not specified for stage box(es). Are these intended to be provided under - Appendix A - 27 41 20 - AUDITORIUM Item #69? If so, please specify quantity of intended accessory/loose item patch cables.

    - ABD RESPONSE: Verify with SPS Purchasing that the correct version of 27 41 20 – Appendix 'A' has been issued. The "Issued for Bid" version should denote quantities required. Quantities of patch cables should only be provided as needed for day-one fixed and assigned portable devices. For stage box, provide a Rapco DURACAT-50NB45 type or similar black ruggedized CAT6 with Ethercon terminations, under Item #66, miscellaneous.