



TOWN OF NOLENSVILLE, TENNESSEE
REQUEST FOR PROPOSAL FOR
ROCKY FORK ROAD IMPROVEMENTS AT NEWSOM LANE
ADDENDUM #2

Issued: August 31, 2026

Proposals Due: On or Before September 3, 2026 at 2:00pm CDT

Item #1 – Plans Revision

The following plans sheets have been added or revised:

- Added
 - SIGN-2
- Revised
 - 1A
 - 2
 - 2-1
 - 2C
 - 2C1
 - 2F

Bidders may contact Justin Eckel, PE at STV Engineers, Inc. at justin.eckel@stvinc.com for a copy of the final plans.

Item #2 – Questions and Answers

Questions Received via Email from August 20, 2026 to August 28, 2026:

1. Will a new bid form be sent out? *RESPONSE: Yes. A final bid form will be emailed to all bidders that have previously requested plans.*
2. Are you going to issue a new bid form that includes the items associated with the force main? *RESPONSE: A new bid form will be issued but not one that includes individual pay items for the force main sewer. Per addendum #1, this work will be paid for under Item No.*

797-99.01, Force Main Sewer Extension, LS. The Contractor is responsible for determining the quantities required for completion of this work.

3. You have items 611-01.02 and 793-14.06 that are associated with the manhole. Are you doing that to give the city the option to precast or cast-in-place? *RESPONSE: Yes, the Contractor has the option to precast or cast this work in place. Item No. 793-14.06 is removed in the final plans and footnotes to this effect have been added to Item No. 611-01.02.*
4. Can you confirm the Liquidated Damages for this project? *RESPONSE: Liquidated damages will follow Section 108.09 of the TDOT Standard Specifications Section 108.09.*
5. Can you clarify the standard drawing and structure depth for 611-01.02 (Manholes, >4'-8' Depth)? I don't see that listed in the plans or the table for storm structures. *RESPONSE: This bid item is intended to cover the removal of the top of the existing area drain located at Newsom Lane STA 200+34.64 and replacement with a new collar, box top, and manhole assembly to bring the existing manhole to the proper elevation. The final plans have added clarifying footnotes and Item No. 793-14.06 has been removed.*
6. That cast in place structure is going over the top of twin 42" RCP pipes. Can this potentially be a precast structure instead and also the 5' 2" x 5' 2" ID structure based off the standard drawing provided would not fit over twin 42" RCP. Please advise? *RESPONSE: See questions 3 and 6.*
7. What will the working days/hours be? Will there be any specific days/hours where work will not be allowed? *RESPONSE: Working days are generally Monday thru Saturday 7:00AM to 7:00PM (or dusk) and Sunday 9:00AM to 7:00PM (or dusk). Contractor may not work on holidays observed by the Town of Nolensville. Working hours outside of these windows may be requested by the Contractor in writing for approval at least seven (7) days prior to the requested deviation from the hours listed. Approval of work-hour deviations is at the sole discretion of the Town of Nolensville.*

See also Question 8 from Addendum #1 regarding lane closures.

8. Will night shift work be allowed? *RESPONSE: Night work may be requested by the Contractor and will be evaluated on a case-by-case basis at least seven (7) business days prior to the day(s) being requested. Approval is at the sole discretion of the Town of Nolensville.*
9. Are you willing to distribute a plans holders list? *RESPONSE: This information will not be provided.*