

**Arlington Public Schools**  
**2024 Capital Levy Proposal**

| Site                  | Project Name  | Scope  | Cost Estimate | Site Total Investment |
|-----------------------|---|--|---------------|-----------------------|
| Arlington High School | Main Building Roofing   | Full reroof, excluding new classroom addition, scene shop and south side of BPAC.  | 5,849,255     |                       |
| Arlington High School | Gutters Main Building, BPAC, and CTE Shop                         | Increase size of downspout serving commons. Add second downspout at BPAC. Add capacity to gutter-downspout system on east side of commons  | 30,901        |                       |
| Arlington High School | Building Structure  | Repair floor settlement at freezer and cooler in kitchen.  | 90,321        |                       |
| Arlington High School | Flooring Main Building  | Seam repair kitchen flooring   | 2,664         |                       |
| Arlington High School | Main Gym and Aux Gym Flooring                                     | Full replacement using new and salvaged flooring. Install sleeper system allowing for venting. Apply vapor block to slab. Finish flooring. | 700,359       |                       |
| Arlington High School | Water Heaters Main Building M13, CTE Building M14, Grandstand M15 | Main bldg.: replace 1 kitchen water heater. Replace 2 water heaters serving locker rooms   | 90,601        |                       |
| Arlington High School | Fiber Homeruns to IDF Rooms Connected by Cable                    | Homeruns to 1 MDF, 8 IDF rooms, network  | 132,200       | 6,896,301             |